

Abstract Notification dated 5th February 1938.

The attention of the public is invited to the detailed notification published on pages 183-184, Part VI of the *Mysore Gazette* dated the 10th February 1938 regarding the auction sale of timber in the following depots:—

Tarikere	17th and 18th March 1938.
Bhadravati	14th March 1938.
Channagiri	7th March 1938.
Ubrani	9th March 1938.

M. G. VENKATA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT**BUILDINGS DIVISION, BANGALORE.***Abstract Notification dated the 4th February 1938.*

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing a Police Station at Ooparpet, Bangalore City, published in pages 186-187, Part VI of *Mysore Gazette*, dated 10th February 1938.

The last date for the receipt of the tender is 25th February 1938.

B. R. GARUDACHAR,
Executive Engineer.

BANGALORE DIVISION.*Notification dated 18th February 1938.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 p.m. on 14th March 1938, for restoring and improving the Yelachigere Major tank, Reg. No. 21 of Nelamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 480 (four hundred and eighty only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring and Improving the Yelachigere Major tank, Reg. No. 21 of Nelamangala Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond after depositing an additional sum of Rs. 480, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring and improving Yelachigere Major Tank, Register No. 21 of Nelamangala Taluk.

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
	<i>Bund.</i>			Rs. a. p.		
1	Cutting grips and clearing jungle ..	Grade	18	2 8 0		
2	Earthwork to bund with the required lead and lift including watering and tamping ..	C.yd.	11,266	0 4 0		
3	Lead and consolidation charges for the earth available from Waste Weir used to bund ..	"	2,500	0 1 0		
4	Earthwork excavation of puddle trench ..	"	1,241	0 4 0		
5	Puddle with clay and gravel mixed in equal proportion with the required lead lift and consolidation ..	"	1,241	0 10 0		
6	Rough stone revetment with the required lead lift including jelly backing and jelly wedging ..	"	939	1 8 0		
7	Turfing the slopes of bund and watering till it is satisfactory ..	S.yd.	7,015	0 1 0		
8	Removing and refixing old grade stones on new bed slabs including painting and figuring ..	Each	15	0 2 0		
9	Providing and fixing new grade stones including bed slabs, cutting figures and painting, etc., complete ..	"	4	2 0 0		
10	Do B. M. stones do ..	"	2	2 8 0		
11	Refixing the gauge stone with bed slab brick masonry, etc., complete including painting, figuring, etc., complete ..	"	1	3 0 0		
12	Refixing Register No. stone on new bed slab including painting, figuring, etc., complete ..	"	1	1 0 0		
13	Providing and fixing new index stones including painting ..	"	19	0 5 0		
	<i>Waste Weir 140 feet long.</i>					
1	Earthwork excavation in hard soil and using earth to bund and training bank ..	C.yd.	3,125	0 3 0		
2	Burnt brick in surki mortar ..	C.ft.	991	0 4 6		
3	Burnt stone slabs new 6" thick, one line dressed and fixed in surki mortar ..	S.ft.	168	0 6 0		
4	Removing and refixing burnt stone slabs old in surki mortar ..	"	166	0 1 6		
5	Providing and fixing joggle joints ..	Each joint }	23	0 8 0		
6	Burnt size stone in surki mortar ..	C.ft.	133	0 5 0		
7	Surki mortar plastering ..	Sqr.	9.99	3 4 0		
8	Cement pointing to stone work ..	"	1.78	3 4 0		
9	Removing and resetting rough stone work old with new jelly backing and jelly weeding, etc., complete ..	C.yd.	144	0 12 0		

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
	<i>Sluice at R. L. 44.00.</i>			Rs. a. p.		
1	Earthwork, cut opening the bund and forming a ring bund in front	C.yd.	249	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	234	0 3 9		
3	Burnt brick in surki mortar	"	506	0 4 6		
4	Burnt stone slabs 6" thick, one line dressed and fixed in surki mortar	S.ft.	178	0 6 0		
5	Providing and fixing jallywood plug and L iron rod 2" x 3/8" in section with locking arrangements, etc., complete	Each	1	20 0 0		
6	Cutting holes in slab	"	4	1 0 0		
7	Plastering with surki mortar	Sqr.	6.86	3 4 0		
8	Refilling the cut earth including consolidation	C.yd.	249	0 4 0		
9	Gravel backing	C.yd.	40	0 8 0		
10	Removing and resetting old stone work with new jelly backing and jelly wedging	"	18	1 0 0		
11	Providing, laying and jointing with cement 9" Dr. C. I. Bhadravati pipes (Pipes will be supplied Departmentally)	R.ft.	48	2 8 0		
	<i>Restoring silt drains 1, 2 & 3.</i>					
1	Earthwork, removing silt and sand	C.yd.	528	0 2 3		
2	Earthwork to bund of feeder with watering and tamping	"	1,152	0 4 0		
3	Rough stone work new with the required lead and lift with jelly backing and jelly wedging	"	221	1 8 0		
4	Puddle mixed with clay and gravel in equal proportion for the breach	"	47	0 8 0		
5	Turfing and watering till it is satisfactory	S.yd.	483	0 1 0		
6	Earthwork excavation	C.yd.	8	0 4 0		
7	Burnt brick in surki mortar	C.ft.	242	0 4 6		
8	Burnt stone slabs 6" thick, one line dressed and fixed in surki mortar	S.ft.	77	0 6 0		
9	Plastering with surki mortar	Sqr.	3.00	3 4 0		
10	Benching rock	S.ft.	20	0 4 0		
11	Providing joggle joints	Each	7	1 0 0		
12	Earthwork done at the relieving weirs will be used for the bund and payment will be made under Bund of feeder channel					

N. LAKSHMINARASIMHAIA,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated the 5th February 1938.

The attention of the public is invited to the Notification published in pages 198-202, Part VI of the *Mysore Gazette*, dated the 10th February 1938, calling for sealed tenders for the construction of Krishnarajendra Police Station at Mysore.